

INVITATION TO BID

LARKSPUR CIVIC DEVELOPMENT AUTHORITY

Solicitation No.	LCDA-MEP-2026-08
Project	Larkspur Civic Center Annex Mechanical Package
Owner	Larkspur Civic Development Authority
Project Location	Denver, CO
Trades Required	HVAC and controls

SECTION 1 - SCOPE OF WORK

The Work comprises the complete mechanical package for the Civic Center Annex, including four (4) custom air handling units, associated hydronic heating and chilled water piping within the mechanical penthouse, VAV terminal units throughout the occupied floors, and a new direct digital control system tied to the Authority existing campus front end. Plumbing scope is bid under a separate package and is excluded here.

SECTION 2 - SCHEDULE OF QUANTITIES

Item	Description	Unit	Qty
23 73 13	Custom indoor air handling unit, 12,000 CFM	EA	4
23 36 00	VAV terminal unit with hot water reheat coil	EA	86
23 21 13	Hydronic piping, welded carbon steel, 4 in.	LF	1,240
23 09 23	DDC controller, field-mounted	EA	94
23 05 93	Testing, adjusting and balancing, complete system	LS	1

Quantities shown are for bidder convenience. Bidders are responsible for verifying all quantities from the contract drawings.

SECTION 3 - PROJECT SCHEDULE AND BUDGET

Engineer's estimate	\$1,200,000
Bid due	September 29, 2026 at 2:00 PM MT
Pre-bid walk-through	September 15, 2026 at 8:30 AM
Construction start	November 1, 2026
Substantial completion	February 28, 2027

SECTION 4 - BONDING AND INSURANCE

Requirement	Amount
Bid bond	5% of total base bid
Performance bond	100% of contract sum
Payment bond	100% of contract sum
Commercial general liability	\$2,000,000 per occurrence

SECTION 5 - CONTACT

Direct all questions in writing to Ingeborg Talamantez-Fyfe, Contracting Officer.